


OFFICE OF THE MARION COUNTY SURVEYOR  
SECTION RECORD CORNER  
SECTION 33 TOWNSHIP 16 RANGE 4  
DATE: 10-29-08  
PARTY CHIEF: Wilcoxen  
CREW: \_\_\_\_\_  
TYPE OF MARKER: Set Harrison  
METHOD OF ESTABLISHMENT: County: 1-14-04

IN. S.P.C. E ZONE NAD '83  
NAME: 16043301  
N: 504965.9478(m)  
E:   62685.8631(m)



CORNER HISTORY: No reference per 3"x5" tie cards. No reference per the Marion County Atlas pg.11. Reference found per the Center Township Legal Survey Book pg. 15 survey by O. W. Voorhis dated 6-19-1877 called a 10" ash N 33 1/2 W and 51 1/2 links. Reference dated 3-9-76 by Wilcoxen called brass bolt. Reference dated 9-26-86 by Gries called same. Reference 8-23-97 by Wilcoxen called PK nail found. Reference dated 1-14-04 by Wilcoxen called PK nail found. Reference dated 10-29-08 by Wilcoxen set Harrison by ties and GPS no other points were found.

16043301

REF.	DISTANCE	DESCRIPTION
1.	69.30'	PK nail w/shiner NW PwP#1-472A
2.	87.50'	Cut 'x' NF bolt of railroad crossing sign base
3.	71.73'	PK nail w/shiner SW guide pole 6"up
4.	74.75'	PK nail W PwP#128-471B 8"up
5.	51.41'	Cut 'x' SE inlet
6.	52.55'	Top nut of fire hydrant
7.	144.56'	SE ace of stucco building